



## Notice of Discontinuation

**Company:** KYCON, Inc.  
305 Digital Dr.  
Morgan Hill, CA 95037  
USA  
408-494-0330

**4/30/19**

Re: **EOL**

**Part number: KMDVLX-xS-N**

The tooling for the above part series is worn. We will offer a last time buy through 5/31/19 (longer if we have stock)

We are in the process of retooling. The part numbers will be different since parts are not identical. A redline is attached with this notification.

See below for the status of the tooling.

KMDVLX-3S-N-1 new tooling in process – contact Kycon for estimated sample availability date

KMDVLX-4S-N-1 new tooling complete – samples available

KMDVLX-5S-N-1 new tooling in process – contact Kycon for estimated sample availability date




KMDVLX-6S-N-1 new tooling complete – samples available

KMDVLX-7S-N-1 new tooling complete – samples available

KMDVLX-8S-N-1 new tooling complete – samples available

KYCON, Inc. 305 Digital Drive, Morgan Hill, CA 95037 (408)494-0330

vs. KMDVLX-xS-N




All pins now same length

Phosphor Bronze

**Materials and Finish**  
 Housing: PBT Thermoplastic  
 Color: Black  
 Shield: Brass, Matte Tin Plated  
 Contact Material: Brass, Silver Plated

**Electrical Characteristics**  
 Rated Current: 2A Max.  
 Rated Voltage: 12V DC  
 Insulation Resistance: 50 Megohms Min. at 500V DC  
 Contact Resistance: 30 milliohms Max.  
 Dielectric Withstanding Voltage: 500V AC for 1 Minute

**Mechanical Characteristics**  
 Insertion Force: 0.3kg-3.0kg  
 Withdrawal Force: 0.3kg-3.0kg  
 Durability Rating: 5000 Mating Cycles Min.  
 Operating Temperature: -25°C to +85°C



RoHS COMPLIANT



Tolerances:  
 X.X ± 0.35  
 X.XX ± 0.25  
 Unless Stated Otherwise

REV.	DATE	DESCRIPTION	REV. BY	CHK. BY	DRAWN BY	DATE
01	05/17/18	Mini-Din, Vertical Mount	D. Serrato	D. Serrato	D. Serrato	05/17/18
02	05/17/18	Revised Drawing	D. Serrato	D. Serrato	D. Serrato	05/17/18

KMDVLX-xS-N-1

Mini-Din, Vertical Mount  
 Snap and Lock, RoHS Compliant



Signature: \_\_\_\_\_

*Full Sam*

Name: Jill Scarnecchia      Phone: 408-494-0330